



DeWitt County Board

201 W. Washington St.
P.O. Box 439
Clinton, IL 61727
(217) 935-7770

Terry Ferguson, Chairman

Melonie Tilley, Vice-Chair

Dee Dee Rentmeister, County Administrator

October 25, 2022

The DeWitt County Marina Committee is taking bids for float replacements on docks 1,2,3 and 5 at Clinton Lake Marina. Location is 6599 Sailboat Rd, Weldon, IL.

Bids will be received until 3:00 p.m., November 3, 2022 either electronically or by mail. If submitting by email send to Dee Dee Rentmeister at drentmeister@dewittcountyil.gov or by mail to Dee Dee Rentmeister, DeWitt County Building, PO Box 439, Clinton, IL 61727. Bids will be opened at that time and reviewed for action by the County Board at it's regular scheduled meeting on November 23, 2022 at 6:00 p.m.

See attached specifications along with an aerial view of Clinton Lake Marina.

The County reserves the right to reject any and all bids.

Any questions may be directed to Dan Matthews at dmatthews@dewittcountyil.gov.

Dee Dee Rentmeister
County Administrator

Clinton Lake Marina Dock Project,

Bid to include all hardware, floats, shipping, installation and removal of all old floats and materials from lake into customer supplied dumpsters.

Project completion required by 12/31/2022.

Terms included in bid, "Removal of old Floatation". Current docks contain both 12" of Styrofoam floatation material with a 12" float fastened below the Styrofoam. All Styrofoam must be removed and replaced with 24" tall floats.

Dock 1:

- Add bracing to ramp floatation cage to remove spacer.
- Remove old floatation and install new ramp float tank 3' x 8' x 24"
- Remove old floatation and install 2 new 3' x 6' x 24" float tanks on section of dock attached to Ramp.
- All new hardware required.

Dock 2:

- Remove old floatation and install new float tanks using 18-3' x 8' x 24" and 8-4' x 10' x 24" float tanks.
- All new hardware required.

Dock 3:

- Remove old floatation and install new float tanks using 20-3'x8'x24" and 1-4'x10'x24" float tank and 10-4'x8'x24" float tanks.
- All new hardware required.

Dock 5:

- Remove old floatation and install new float tanks using 2-3'x10'x24" floats.
- All new hardware required.

Preferred Floats, Eagle Float tanks from Hendren Plastic with a 15 year manufacturer warranty.

